


POLE FOUNDATION SCHEDULE

POLE DESIGNATION	FORCES (1)			DRILLED PIER		
	MOMENT (M) FT-LBS	SHEAR (V) LBS	VERTICAL (P) LBS	DIAMETER INCHES	EMBEDMENT DEPTH (3.)	CONCRETE BACKFILL YD ³ (2.)
F1	253,588	4,018	6,874	36	20'-0"	2.7
F2	224,780	3,643	6,622	36	20'-0"	2.7
F3, F4	174,695	2,897	4,682	30	18'-0"	1.6

- ASD LOAD COMBINATION D + 0.6W. VERTICAL FORCE IS WEIGHT OF DRESSED POLE (DOES NOT INCLUDE PRECAST BASE WEIGHT).
- MINIMUM CONCRETE BACKFILL VOLUME, SITE CONDITIONS MAY REQUIRE ADDITIONAL BACKFILL.
- WEATHERED SHALE IS EXPECTED WITHIN THE TOP 5'-0" BELOW GRADE - SEE SOIL BORINGS. INSTALLATION EQUIPMENT MUST BE CAPABLE OF PENETRATING SHALE TO REACH EMBEDMENT DEPTHS SHOWN.



POLE FOUNDATION ELEV.

SCALE: NOT TO SCALE

SOIL BACKFILL NOTE:
THE TOP TWO FEET OF ANNULUS SHALL BE BACKFILLED WITH SOIL, WITH A CLASSIFICATION OF CLASS 5 (TABLE 1806.2) OR BETTER. COMPACTION, 95% FOR COHESIVE SOIL AND 98% FOR A COHESIONLESS SOIL BASED UPON STANDARD PROCTOR TESTING (ASTM D698).

PRECAST BASE IDENTIFICATION

PRECAST BASE TYPE	PRECAST BASE WEIGHT	PRECAST BASE LENGTH	PROJECTION ABOVE GRADE	STANDARD EMBEDMENT	OUTSIDE DIAMETER
6B	6,930 LBS	26'-1"	8'-1"	18'-0"	20.56"
7B	10,160 LBS	27'-10"	7'-10"	20'-0"	23.75"

POLE IDENTIFICATION

POLE DESIGNATION	POLE TYPE	PRECAST BASE TYPE	FIXTURE CONFIGURATION (FIX. PER XARM)	FIXTURE AND ACCESSORIES EPA (FT ²)
F1	LSS90C	7B	14 (6+5)	78.2
F2	LSS90C	7B	14 (6+5)	62.3
F3, F4	LSS90B	6B	15 (6+5)	41.8

- POLES F1 & F2 HAVE (2) COMMUNITY R2 SPEAKERS AT 80'-0" AGL INCLUDED IN EPA ABOVE.
- POLES F1 & F2 HAVE (1) COMMUNITY R2 SPEAKER AT 76'-0" AGL INCLUDED IN EPA ABOVE.
- POLE F1 HAS (2) COMMUNITY R2 SPEAKERS AT 72'-0" AGL INCLUDED IN EPA ABOVE.
- POLES F1 & F2 HAVE (1) MUSCO LED FIXTURE AT 65'-0" AGL INCLUDED ABOVE.
- POLES F3 & F4 HAVE (2) MUSCO LED FIXTURES AT 65'-0" AGL INCLUDED ABOVE.
- POLES F1 & F2 HAVE (2) MUSCO LED FIXTURES AT 15'-6" AGL INCLUDED ABOVE.
- POLES F3 & F4 HAVE (2) MUSCO LED FIXTURES AT 25'-0" AGL INCLUDED ABOVE.

DESIGN NOTES

DESIGN PARAMETERS:
WIND: $V = 115 \text{ MPH}$, $V_{\text{asd}} = 89 \text{ MPH}$ (EXPOSURE C, RISK CATEGORY II) PER INTERNATIONAL BUILDING CODE, 2018 EDITION (ASCE 7-16). DESIGN WIND PARAMETERS ARE AS NOTED. ACTUAL EXPOSURE MUST BE VERIFIED FOR THE SITE BY THE PROPER GOVERNING OFFICIAL.

GEOTECHNICAL PARAMETERS:
ALLOWABLE END BEARING SOIL PRESSURE: 8,000 PSF
ALLOWABLE LATERAL SOIL BEARING PRESSURE:
0 PSF/FT (GRADE TO -3'-0"); 100 PSF/FT (-3'-0" TO -5'-0"); 400 PSF/FT (BELOW -5'-0")
IN ACCORDANCE WITH THE 2018 EDITION OF THE INTERNATIONAL BUILDING CODE, CHAPTER 18.

DESIGN SOIL PARAMETERS ARE AS NOTED. ACTUAL ALLOWABLE SOIL PARAMETERS MUST BE VERIFIED ON SITE. REFERENCE SOILS AND FOUNDATION REPORT, NO. 19-C-32, PREPARED BY SOR CONSULTING ENGINEERS, INC.; CEDAR GROVE, NJ.

A GEOTECHNICAL ENGINEER OR REPRESENTATIVE OF IS RECOMMENDED (NOT REQUIRED) TO BE AVAILABLE AT THE TIME OF THE FOUNDATION INSTALLATION TO VERIFY THE SOIL DESIGN PARAMETERS AND TO PROVIDE ASSISTANCE IF ANY PROBLEMS ARISE IN FOUNDATION INSTALLATION.

ENCOUNTERING SOIL FORMATIONS THAT WILL REQUIRE SPECIAL DESIGN CONSIDERATIONS OR EXCAVATION PROCEDURES MAY OCCUR. POLE FOUNDATIONS WILL NEED TO BE ANALYZED ACCORDING TO THE SOIL CONDITIONS THAT EXIST. IF ANY DISCREPANCIES OR INCONSISTENCIES ARISE, NOTIFY THE ENGINEER OF SUCH DISCREPANCIES. FOUNDATIONS WILL THEN BE REVISED ACCORDINGLY. REVISIONS WILL BE ANALYZED PER RECOMMENDATIONS DIRECTED BY A REGISTERED ENGINEER.

ALL EXCAVATIONS MUST BE FREE OF LOOSE SOIL AND DEBRIS PRIOR TO FOUNDATION INSTALLATION AND CONCRETE BACKFILL PLACEMENT. TEMPORARY CASINGS OR DRILLERS SLURRY MAY BE USED TO STABILIZE THE EXCAVATION DURING INSTALLATION. CASINGS MUST BE REMOVED DURING CONCRETE BACKFILL PLACEMENT. CONCRETE BACKFILL MUST BE PLACED WITH A TREMIE WHEN SLURRY OR WATER IS PRESENT WITHIN THE EXCAVATION OR WHEN THE FREE DROP EXCEEDS 6'-0".

CONTRACTOR MUST BE FAMILIAR WITH THE COMPLETE SOIL INVESTIGATION REPORT AND BORINGS, AND CONTACT THE GEOTECHNICAL FIRM (IF NECESSARY) TO UNDERSTAND THE SOIL CONDITIONS AND THE POSSIBILITY OF GROUND WATER PUMPING AND EXCAVATION STABILIZATION OR BRACING DURING PRECAST BASE INSTALLATION AND PLACEMENT OF CONCRETE BACKFILL.

CONCRETE:
CONCRETE SHALL BE AIR-ENTRAINED AND HAVE A MINIMUM COMPRESSIVE DESIGN STRENGTH AT 28 DAYS OF 3,000 PSI. 3,000 PSI CONCRETE SPECIFIED FOR EARLY POLE ERECTION, ACTUAL REQUIRED MINIMUM ALLOWABLE CONCRETE STRENGTH IS 1,000 PSI. ALL PIERS AND CONCRETE BACKFILL MUST BEAR ON AND AGAINST FIRM UNDISTURBED SOIL.

GENERAL NOTES:
FIXTURES MUST BE LOCATED TO MAINTAIN 10'-0" MINIMUM HORIZONTAL CLEARANCE FROM ANY OBSTRUCTION. ENGINEER MUST BE NOTIFIED IF FOUNDATIONS ARE NEAR ANY RETAINING WALLS OR WITHIN / NEAR ANY SLOPES STEEPER THAN 3H : 1V. POLES, FIXTURES, PRECAST BASES, ELECTRICAL ITEMS AND INSTALLATION PER MUSCO LIGHTING.

LACINA ENGINEERING, LLC

114 NICHOLAS DRIVE
MARSHALLTOWN, IA 50158

OFFICE NUMBER: 641-752-6334


EMAIL: MSL.INFO@SEPC.BIZ

CERTIFICATE OF AUTHORIZATION NUMBER:
24GA28206700

Kyle G. Lacina
10-30-2019

KYLE G. LACINA - NEW JERSEY
PROFESSIONAL ENGINEER NO.: 45743

PISCATAWAY HS
FOOTBALL FIELD
RELIGHT
PISCATAWAY, NJ



DESIGNED BY: MLP
DRAWING BY: MLP
CHECKED BY: KGL
REVISIONS:

DRAWING TITLE:
POLE AND FOUNDATION
SCALE: SEE PLAN
NOTES:
SCAN #196598B

PROJECT NUMBER
196598

DATE
30 OCTOBER 2019

DRAWING NUMBER
C1

OF ONE